



SITE #4 (96A AVE)
 MILLING DEPTH= 45 mm
 OVERLAY DEPTH= 50 mm
 PAVEMENT AREA= 4,900 m²
 PQI= 3.9

SITE #3 (HARBOUR POOL ACCESS ROAD)
 MILLING DEPTH= 45 mm
 OVERLAY DEPTH= 50 mm
 PAVEMENT AREA= 3,800 m²
 PQI= -

SITE #2 (93 AVE)
 MILLING DEPTH= 45 mm
 OVERLAY DEPTH= 50 mm
 PAVEMENT AREA= 3,100 m²
 PQI= 2.7

SITE #5 (99 AVE-1)
 MILLING DEPTH= 45 mm
 OVERLAY DEPTH= 50 mm
 PAVEMENT AREA= 5,600 m²
 PQI= 3.7
 CURB & GUTTER WORK

SITE #6 (99 AVE-2)
 MILLING DEPTH= 45 mm
 OVERLAY DEPTH= 50 mm
 PAVEMENT AREA= 4,300 m²
 PQI= 2.6

SITE #1 (93A AVE/79ST/93AVE)
 MILLING DEPTH= 45 mm
 OVERLAY DEPTH= 50 mm
 PAVEMENT AREA= 4,000 m²
 PQI= 3.2

SITE #7 (101 ST)
 MILLING DEPTH= 45 mm
 OVERLAY DEPTH= 50 mm
 PAVEMENT AREA= xx m²
 PQI= 6.0
 LEFT TURN IMPLEMENTATION

SITE #H2 (HWY-15 EB)
 MILLING DEPTH= 70 mm
 OVERLAY DEPTH= 75 mm
 PAVEMENT AREA= 17,000 m²
 PQI= 4.1/7.0

SITE #H1 (HWY-21 NB/SB)
 MILLING DEPTH= 70 mm
 OVERLAY DEPTH= 75 mm
 PAVEMENT AREA= 19,000 m²
 PQI= 5.0

2020 PROGRAM

All roads subject to change based on detailed assessment and tendered prices



CITY OF FORT SASKATCHEWAN

2020 LOCAL ROAD REHABILITATION PROGRAM

Overall Location Plan

-	Date: APRIL 2020	Dwg #:
SCALE = NTS	Drawn: PM	OVERALL